NATIONAL ENGINEERING SERVICES PAKISTAN (PVT) LIMITED
NESPAK HOUSE: 1-C, Block-N, Model Town Extension, Lahore - 54700, Pakistan
Established in 1973

Ref: 5140/024/MAN/01/0779 Date: November 06, 2026

CONSTRUCTION OF JUDICIAL TOWER-I, JUDICIAL TOWER-II, JUDICIAL TOWER-III, LAHORE

GEOTECHNICAL INVESTIGATIONS

Request for Quotations for Geotechnical Investigation (Field and Laboratory Works for Triaxial Testing)

Dear Sir,

Quotations (inclusive of all taxes) with validity for ninety (90) days from opening date, are invited through **EPADS v2.0** based on the attached Bill of Quantities and Qualification Criteria, from Applicants for conducting the geotechnical investigation for the subject project. This procurement is being carried following the method of procurement, **shopping through request for quotations under Rule 32(1)(b)** of the Public Procurement Rules, 2026.

The completion of the field and laboratory work must adhere to the following time schedule:

Time for Completion of Field Investigation	Time for Completion of Laboratory Testing	Overall Completion Time
Four (04) days	Twenty-one (21) days	Twenty-five (25) days

The successful Applicant shall mobilize to the site within one day after receiving the Letter of Award/Acceptance. Laboratory testing shall be conducted at NESPAK's approved laboratory. The successful Applicant shall also coordinate with the laboratory to ensure timely testing and provide field logs and laboratory results to NESPAK within the contract period.

Payment will be based on actual work performed, measured and certified by the Engineer at the rates quoted in your quotation.

Quotations (inclusive of all taxes) and required technical documents must be submitted through **EPADS v2.0** by **1400 hours** on or before **November 11, 2026**. Quotations will be opened electronically on EPADS v2.0 on the same day at **1430 hours**. However, final decision to accept/reject any or all the quotations as per PPRA rules solely lies with the undersigned. The entire work shall be carried out in accordance with the requirements of the General Bidding Documents for Geotechnical Investigations available at NESPAK website (www.nespak.com.pk).

for National Engineering Services Pakistan (Pvt.) Limited

(MUHAMMAD ABDUL NASIR)
General Manager/Acting Head
Geotechnical & Geoenvironmental Engineering Division

Telephone : +92-42-99090000 Fax : +92-42-99231950
E-mail : info@nespak.com.pk P.O.Box : 1351, Lahore, Pakistan
Website : www.nespak.com.pk
TÜV AUSTRIA

CONSTRUCTION OF JUDICIAL TOWER-I, JUDICIAL TOWER-II, JUDICIAL TOWER-III, LAHORE

GEOTECHNICAL INVESTIGATIONS
(Field and Laboratory Works for Triaxial Testing)

QUALIFICATION CRITERIA

Qualification will be based on the criteria outlined below. Quotations will be deemed **"Acceptable"** only if Applicants meet all criteria from Sr. No. 1 to 8. However, the Employer reserves the right to waive minor deviations that do not significantly impact the Applicant's ability to perform the contract.

The capabilities of a subcontractor will not be considered for the Applicant's compliance with qualifying criteria. However, for joint ventures, the qualifications of all partners will be taken into account.

Applicants are required to fill the **"Applicant's Response"** column for each compliance requirement and submit the requisite documents for the evaluation.

1. General Information

The Applicant shall provide general information as listed below:

Field	**Details**
Name of Firm	
Head Office Address	
Contact Details	

2. Registration of the Firm

Criteria	**Compliance Requirement**	**Applicant's Response (Yes/No)**
Valid registration with Pakistan Engineering Council (PEC) with active status. **Attach registration certificate**	Must meet	
Valid registration with Federal Board of Revenue (FBR) with active status. **Attach registration certificate**	Must meet	
Valid registration with concerned Provincial Revenue Authority with active status. **Attach registration certificate**	Must meet	

Applicant's Signature _____.

Applicant's Stamp _____.

3. Experience of the Firm

Criteria	Compliance Requirement	Applicant's Response (Yes/No)
Completed at least three (3) geotechnical investigation projects of similar nature within the last three (3) years, each with a value of at least Rs. one (1) million. **Attach letter of awards/project completion certificates**	Must meet	

4. Personnel Capabilities

The Applicant is required to have qualified personnel in the following positions.

Criteria	Compliance Requirement	Applicant's Response (Yes/No)
One (1) site supervisor with a minimum qualification of BSc in Civil Engineering or BSc in Geological Engineering or MSc in Geology or equivalent, along with at least two (2) years of experience. **Attach CV of the personnel**	Must meet	

5. Equipment Capabilities

The Applicant should own or have access to the following equipment, fully operational, available for deployment:

Criteria	Compliance Requirement	Applicant's Response (Yes/No)
Straight Rotary Drilling rig complete in all respects including drilling rods, bits, mud pumps as per the attached BOQ.	Must meet	
Casing of various diameters and lengths for all types of boring, along with casing bits, as per site requirements.	Must meet	
Shelby/Denison/Pitcher samplers	Must meet	
UDS tubes & Split Spoon Samplers	Must meet	
Hydraulic jacks with all accessories for the extraction of casings	Must meet	
Wooden box for the preservation of undisturbed soil samples	Must meet	
Transport for mobilization of equipment	Must meet	

Applicant's Signature _____.

Applicant's Stamp _____.

6. Financial Capabilities

Criteria	Compliance Requirement	Applicant's Response (Yes/No)
An average annual turnover of at least Rs. one (1) million from geotechnical investigation works over the past three (3) years.	Must meet	
A letter from the Applicant's bank confirming the existence of an active account in good standing for at least the past twelve (12) months. **Attach bank account maintenance letter**	Must meet	

7. Litigation History

Criteria	Compliance Requirement	Applicant's Response (Yes/No)
Provide details of any litigation or arbitration from contracts completed or ongoing in the last three (3) years if applicable. If no litigation, provide a statement of no litigation on firm letterhead. A recurring/extensive history of litigation against the Applicant may lead to the rejection of the application.	Must provide	

8. Health, Safety and Environmental Standards

Criteria	Compliance Requirement	Applicant's Response (Yes/No)
The Applicant must ensure compliance with all relevant health, safety and environmental standards, including the provision of: • First Aid Box • Personal Protective Equipment (PPE) • Standard Operating Procedures (SOPs) • HSE Personnel with a valid HSE Compliance Certificate; **Attach HSE certification**	Must meet	

Applicant's Signature _____.

Applicant's Stamp _____.

Construction of Judicial Tower-I, Judicial Tower-II, Judicial Tower-III, Lahore

BILL OF QUANTITIES FOR GEOTECHNICAL INVESTIGATION
(Field and Laboratory Works for Triaxial Testing)

Sr. No.	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
A.	**FIELD INVESTIGATIONS**				
A1	Mobilization and demobilization of one (01) straight rotary / percussion drilling rigs alongwith allied accessories at site including access, setting up.	L.S.	Job		
A2	Execution of one (01) borehole up to 35 m depth at structure locations below Existing Ground Level in overburden soils, by straight rotary / percussion drilling method including backfilling of boreholes to their original position using cement, sand and bentonite mix. Minimum permissible diameter of borehole is 250 mm for percussion method and 125 mm for straight rotary method.	L.M.	35		
A3	Collection of undisturbed soil samples from borehole through Shelby/Denison/Pitcher samplers, including their waxing, labelling, packing, storage & transportation to an approved testing laboratory. The samples recovery should be more than 70 %.	No.	10		
	Sub-Total A	**Rs.**			

The samples having a recovery of 70% or more will be considered acceptable for laboratory testing.

All soil samples must be labelled, stored and transported as per ASTM. The area ratio and clearance ratio of the thin walled tube, should be in strict compliance with relevant ASTM standard.

The preferred method of drilling is straight rotary. Percussion boring will be used only in case of gravelly strata.

Contractor will be responsible for arrangement of Personnel Protective Equipment (PPEs) such as safety helmets and jackets for NESPAK site supervisory / visiting staff.

Construction of Judicial Tower-I, Judicial Tower-II, Judicial Tower-III, Lahore

BILL OF QUANTITIES FOR GEOTECHNICAL INVESTIGATION
(Field and Laboratory Works for Triaxial Testing)

Sr. No.	Description	Unit	Qty.	Rate	Amount
B.	**LABORATORY TESTING**			(Rs.)	(Rs.)
B1	Sieve analysis	No.	10		
B2	Hydrometer Analysis	No.	4		
B3	Triaxial test on Soil Samples	No.	10		
B4	Oedometer Test	No.	5		
B5	Permeability test Constant Head / Variable Head	No.	4		
	Sub- Total B			**Rs.**	

Name of Laboratory:

Total (A+B)=	**Rs.**	
Say	**Rs.**	